

DTIC FILE COPY

(4)

TECHNICAL REPORT BRL-TR-3081

**BRL****AD-A219 437**

NUMERICAL SIMULATION OF  
SEMI-INFINITE TARGET PENETRATION  
BY CONTINUOUS AND SEGMENTED RODS

J. A. ZUKAS

FEBRUARY 1990

DTIC  
ELECTE  
MAR 16 1990  
S E D

APPROVED FOR PUBLIC RELEASE; DISTRIBUTION UNLIMITED.

U.S. ARMY LABORATORY COMMAND

BALLISTIC RESEARCH LABORATORY  
ABERDEEN PROVING GROUND, MARYLAND

90 03 15 031

## **DESTRUCTION NOTICE**

**Destroy this report when it is no longer needed. DO NOT return it to the originator.**

**Additional copies of this report may be obtained from the National Technical Information Service, U.S. Department of Commerce, 5285 Port Royal Road, Springfield, VA 22161.**

**The findings of this report are not to be construed as an official Department of the Army position, unless so designated by other authorized documents.**

**The use of trade names or manufacturers' names in this report does not constitute indorsement of any commercial product.**

**REPORT DOCUMENTATION PAGE**Form Approved  
OMB No. 0704-0188

Public reporting burden for this collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Washington Headquarters Services, Directorate for Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302, and to the Office of Management and Budget, Paperwork Reduction Project (0704-0188), Washington, DC 20503.

<b>1. AGENCY USE ONLY (Leave blank)</b>		<b>2. REPORT DATE</b> February 1990	<b>3. REPORT TYPE AND DATES COVERED</b> Technical Report, 1988-1989	
<b>4. TITLE AND SUBTITLE</b> Numerical Simulation of Semi-Infinite Target Penetration by Continuous and Segmented Rods.			<b>5. FUNDING NUMBERS</b>	
<b>6. AUTHOR(S)</b> J. A. Zukas				
<b>7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES)</b>			<b>8. PERFORMING ORGANIZATION REPORT NUMBER</b>	
<b>9. SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES)</b> US Army Ballistic Research Laboratory ATTN: SLCBR-DD-T Aberdeen Proving Ground, MD 21005-5066			<b>10. SPONSORING/MONITORING AGENCY REPORT NUMBER</b>  BRL-TR-3081	
<b>11. SUPPLEMENTARY NOTES</b>				
<b>12a. DISTRIBUTION/AVAILABILITY STATEMENT</b> Approved for public release; distribution unlimited.			<b>12b. DISTRIBUTION CODE</b>	
<b>13. ABSTRACT (Maximum 200 words)</b> <p>This report presents results of a numerical study of continuous and segmented rod impacts into semi-infinite steel targets at velocities of 1.5-4 km/s. Variations in segment spacing and number of segments comprising a segmented rod were considered in addition to striking velocity variations. It is found that below 2 km/s, there is no advantage (in terms of penetration) in using segmented rods over continuous rods. However, for striking velocities exceeding 2 km/s, segmented rods show improved penetration with proper adjusment of segment number and spacing.</p>				
<b>14. SUBJECT TERMS</b> terminal ballistics, penetration mechanics, long rod penetration, segmented penetrators, kinetic energy impact			<b>15. NUMBER OF PAGES</b> 32	
			<b>16. PRICE CODE</b>	
<b>17. SECURITY CLASSIFICATION OF REPORT</b> UNCLASSIFIED	<b>18. SECURITY CLASSIFICATION OF THIS PAGE</b> UNCLASSIFIED	<b>19. SECURITY CLASSIFICATION OF ABSTRACT</b> UNCLASSIFIED	<b>20. LIMITATION OF ABSTRACT</b> UL	

# TABLE OF CONTENTS

Page

	LIST OF FIGURES .....	v
	LIST OF TABLES .....	v
1	INTRODUCTION .....	1
2	COMPUTATIONAL RESULTS .....	2
2.1	Effects of Spacing and Velocity .....	2
2.2	Effects of Segment Numbers .....	3
2.3	P/L as a Penetration Performance Measure .....	3
3	CONCLUSIONS .....	4
4	REFERENCES .....	19
	DISTRIBUTION .....	21

Accession For	
NTIS GRA&I	<input checked="" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By	
Distribution/	
Availability Codes	
Dist	Avail and/or Special
A-1	

INTENTIONALLY LEFT BLANK.

## LIST OF FIGURES

<u>Figure</u>	<u>Page</u>
1. Comparison of Penetration Performance of Segmented and Equivalent/Mass-Equivalent Diameter Continuous Rods at Impact Velocities Below 2 km/s . . . . .	5
2. Comparison of Penetration Performance of Segmented and Equivalent/Mass-Equivalent Diameter Continuous Rods at Impact Velocities Above 2 km/s . . . . .	6
3. Computed Deformation of Continuous Rod and Target at 40 $\mu$ s, $V_s = 4$ km/s . . . . .	7
4. Computed Deformation of Continuous Rod and Target at 60 $\mu$ s, $V_s = 4$ km/s . . . . .	8
5. Computed Deformation of Segmented Rod and Target at 20 $\mu$ s, $V_s = 4$ km/s . . . . .	9
6. Computed Deformation of Segmented Rod and Target at 75 $\mu$ s, $V_s = 4$ km/s . . . . .	10
7. Computed Deformation of Segmented Rod and Target at 150 $\mu$ s, $V_s = 4$ km/s . . . . .	11
8. Effect of Segment Number on Penetration for $S/D = 2$ . . . . .	12
9. Impact of 20-Segment Rod at $V_s = 4$ km/s . . . . .	13
10. Penetration Normalized by Collapsed and Extended Projectile Lengths at Two Striking Velocities . . . . .	14

## LIST OF TABLES

<u>Table</u>	<u>Page</u>
1. Penetration Performance of Continuous and Segmented Rods. . . . .	15
2. Effect of Segmentation on Penetration. . . . .	16
3. Comparison of Penetration Data With Different Normalizations . . . . .	17

INTENTIONALLY LEFT BLANK.

## 1. INTRODUCTION

Of late, there has been renewed interest in the performance of segmented long rod penetrators against a variety of armor systems. The potential benefits of segmented penetrators are based on the qualitative advantage of multiple impacts of well-aligned and well-separated penetrator segments when compared to that of a single equivalent penetrator. Eichelberger in 1956 suggested that the penetration performance of a metallic jet with perfectly aligned (Eichelberger 1956), spaced segments could be enhanced by as much as 40% over that of continuous jets. Analytical work by Frank (1985) and numerical simulations by Kucher (1982), de Rosset (1981), de Rosset and Kimsey (1986), Sedgwick et al. (1987) as well as experiments by Charters (1986), Raatschen et al. (1989), Kivity, et al. (1989), Herbette (1989), and others tend to confirm enhanced penetration by well-aligned, properly spaced segments in comparison to equivalent mass and equivalent diameter continuous rods.

Most experiments performed to date have been confined to specific cases with very limited variation of relevant parameters. Calculations have also focused on selected problems. A large number of parameters enter into the determination of penetration performance of segmented rods. A full parametric study remains to be performed.

This report deals with numerical simulation of the penetration of homogeneous, effectively semi-infinite, rolled homogeneous armor (RHA) targets by continuous and segmented tungsten alloy (90% tungsten, 7% nickel, 3% iron, 25% swaged) rods. Calculations were performed varying striking velocity ( $V_s = 1.5, 2, 3, 4$  km/s), segment spacing (1D, 2D, 4D where D = segment diameter), and number of segments (1, 5, 10, 20). The calculations were performed with a local version of the 1978 release of the EPIC-2 code (Johnson 1978), modified to include eroding slide line logic (Kimsey and Zukas 1986). Selected results were verified with HULL code (Matuska and Osborn 1987) computations. Material properties for the tungsten alloy were taken from split-Hopkinson bar data reported by Nicholas (1980), the yield stress taken to be 14.3 kb and the ultimate stress 20 kb at an effective plastic strain of 0.14. The RHA was modeled as an elastic-perfectly plastic material with a flow stress of 8 kilobars.

Two levels of failure may be modeled with the version of EPIC used for these studies, based on user-specified levels of effective plastic strain. When the first level is met, tensile and shear stresses are not allowed to develop in the affected element. The net result is that the element



behaves much like a liquid in that it can support only hydrodynamic compression. When the second level of effective plastic strain is reached, all stresses and pressures are set to zero. Element quantities are no longer included in the simulation, as though total failure had occurred. When this option is invoked, mass and momentum continue to be conserved since the masses and velocities of failed elements are associated with their nodes, and these are tracked throughout the computation. Energy, however, is conserved only approximately since element internal energies are no longer computed. This is a minor concern, however, since this latter value of strain is set at high (150-250%) levels (for lack of better failure models) so that the elements "removed" from the calculation would, in reality, appear as ejecta in ballistic experiments.

## 2. COMPUTATIONAL RESULTS

Figures 1-2 summarize results of calculations showing the effects of the number of segments, segment spacing, and segment velocity on penetration performance. The data for these figures are given in Tables 1-2.

2.1 Effects of Spacing and Velocity. Figure 1 and Table 1 show penetration as a function of segment spacing and velocity for impact velocities to 2 km/s. The measure of penetration is the ratio  $P/L_0$ , where  $P$  represents penetration depth (given in Table 1) and  $L_0$  the initial length of a continuous rod or the collapsed length of a segmented rod. The behavior of a segmented rod with five segments (each with  $L/D = 4$  and segment spacing  $S$  varied between 1-4 projectile diameters,  $D$ ), is contrasted to that of a continuous rod of equivalent mass and diameter. It is clear that at ordnance velocities (striking velocities of 2 km/s or less) the penetration of segmented rods, as measured by  $P/L_0$ , falls below that of a continuous rod for small segment spacings,  $S/D$ , and approaches that of continuous rods as segment spacing is increased.

However, for striking velocities of 3 and 4 km/s, penetration by segmented rods, as measured by  $P/L_0$ , shows improvement over that of continuous rods as a function of both velocity and spacing (see Figure 2). For the situation studied here, gains of about 5% in  $P/L_0$  are achieved by going to segmentation at higher velocities. These gains can be further enhanced by 8-10% by appropriate adjustment of segment spacing. Representative computational results for a continuous rod at 4 km/s are shown in Figures 3-4. Figures 5-7 depict analogous results for an equal mass, equal diameter rod consisting of five segments with  $S/D = 4$ .

The question naturally arises as to whether similar results hold for different segmentations. Figure 8 and Table 2 show (for segmented rods with spacing fixed at  $S/D = 2$ ) the same trends for projectiles with 20 segments (segment  $L/D = 1$ ).

**2.2 Effects of Segment Numbers.** Calculations were also performed to study the effect of the number of segments on normalized penetration. Figure 8 and Table 2 summarize results for a continuous rod (1 segment) as well as rods consisting of 5 (segment  $L/D = 4$ ), 10 (segment  $L/D = 2$ ), and 20 (segment  $L/D = 1$ ) segments striking semi-infinite RHA at velocities of 2, 3, and 4 km/s. Segment spacing was held at 2 diameters ( $S/D = 2$ ). At 2 km/s,  $P/L_0$  is unchanged by varying the number of segments, within the accuracy of the numerical resolution employed in these studies. At the higher velocities, there is a modest gain. For example, for a 20-segment rod at 4 km/s, there is a 20% gain in  $P/L_0$  over that for a continuous rod, 12% for a 10-segment rod, and 6% for a 5-segment rod. For greater spacings, improvements on the order of 30% can be obtained. Recall, however, that these results are for the ideal case -- no initial yaw and segments perfectly aligned. In practice, such conditions are almost never realized, so that these can be considered as an upper limit on possible performance gains.

Typical deformations at various times after impact for a 20-segment rod at a striking velocity of 3 km/s are depicted in Figure 9.

**2.3  $P/L$  as a Penetration Performance Measure.** It is the current custom to cast segmented penetrator results in terms of the nondimensional parameter  $P/L$ , with  $L$  being taken as the collapsed length of a segmented penetrator. It is always dangerous to depict situations involving a complex interaction of a number of variables in terms of a single parameter. That  $P/L$  is an imperfect measure of segmented penetrator performance can be seen in Figure 10 and Table 3, which merely recast the data in Table 2 using two normalization parameters - the collapsed length  $L_0$  and the extended length  $L$ . As Scheffler (1989) has pointed out, the latter is a more natural normalization factor. Many segmented rod configurations are launched with the presence of spacer materials which can affect penetration or are designed to extend in flight. To the degree to which such in-flight extensions are successful, they affect the spacing and, thus, the final penetration. Note from Figure 10 that conflicting conclusions can be drawn about the effectiveness of segmented penetrators depending on the normalization (collapsed or extended length) chosen. At minimum,

segmented rod information should be provided with raw data together with any normalizations deemed appropriate.

### 3. CONCLUSIONS

The simulations performed for this study indicate that, in terms of penetration performance:

- a. There is no advantage to segmented rods over continuous rods at velocities below 2 km/s.
- b. Segmented rods show improved penetration performance over continuous rods with proper adjustments of segment number and spacing for striking velocities exceeding 2 km/s.
- c. The ratio of penetration to penetrator length is inadequate as a measure of performance for a complex impact situation influenced by a large number of parameters. To minimize confusion, raw data should be presented for segmented penetrator impacts. Otherwise, caveat emptor applies! As Scheffler (1989) has pointed out, and as is clear from Figure 10 and Table 3, the ratio of penetration to penetrator length may not be a good indicator of penetrator performance of segmented rods. Depending on the interpretation of length (collapsed or extended), conflicting conclusions can be drawn.




Figure 1. Comparison of Penetration Performance of Segmented and Equivalent/Mass-Equivalent Diameter Continuous Rods at Impact Velocities Below 2 km/s.




Figure 2. Comparison of Penetration Performance of Segmented and Equivalent/Mass-Equivalent Diameter Continuous Rods at Impact Velocities Above 2 km/s.

TIME = 0.00004000

CYCLE = 767




Figure 3. Computed Deformation of Continuous Rod and Target at  
40  $\mu$ s,  $V_s = 4$  km/s.

TIME = 0.00006000

CYCLE = 1096




Figure 4. Computed Deformation of Continuous Rod and Target at  
60  $\mu$ s,  $V_s = 4$  km/s.




Figure 5. Computed Deformation of Segmented Rod and Target at  
20  $\mu$ s,  $V_s = 4$  km/s.



TIME = 0.00007508

CYCLE = 1021




Figure 6. Computed Deformation of Segmented Rod and Target at  
75  $\mu$ s,  $V_s = 4$  km/s.

TIME = 0.00015003

CYCLE = 1919




Figure 7. Computed Deformation of Segmented Rod and Target at  
150  $\mu$ s,  $V_s = 4$  km/s.




Figure 8. Effect of Segment Number on Penetration for  $S/D = 2$ .




Figure 9. Impact of 20-Segment Rod at  $V_s = 4$  km/s.





Figure 10. Penetration Normalized by Collapsed and Extended Projectile Lengths at Two Striking Velocities.

TABLE 1. Penetration Performance of Continuous and Segmented Rods.

Continuous			
Vs km/s		P cm	P/L <sub>o</sub>
1.5		19.2	0.92
2.0		24.0	1.20
3.0		28.2	1.41
4.0		30.4	1.52

Segmented			
V <sub>s</sub> km/s	S/D	P cm	P/L <sub>o</sub>
1.5	1	18.0	0.90
	2	18.4	0.92
	4	19.4	0.98
2.0	1	22.0	1.10
	2	24.0	1.20
	4	24.0	1.20
3.0	1	29.6	1.48
	2	29.7	1.48
	4	30.2	1.51
4.0	1	32.0	1.60
	2	32.0	1.60
	4	33.3	1.67

L<sub>o</sub> = length of continuous rod/collapsed length of segmented rod.

TABLE 2. Effect of Segmentation on Penetration.

$V_s$ km/s	N	P cm	$P/L_o$
2	1	24.0	1.20
	5	24.0	1.20
	10	24.0	1.20
	20	24.0	1.20
3	1	28.2	1.41
	5	29.4	1.47
	10	30.4	1.52
	20	32.0	1.60
4	1	30.4	1.52
	5	32.2	1.61
	10	34.2	1.71
	20	36.5	1.82

N = number of segments (1 = continuous rod).

$L_o$  = length of continuous rod/collapsed length of segmented rod.

TABLE 3. Comparison of Penetration Data With Different Normalizations.

$V_s$ km/s	N	$L_o$ cm	L cm	P cm	$P/L_o$	$P/L$
2	1	20	20	24	1.2	1.2
	5	20	28	24	1.2	0.86
	10	20	38	24	1.2	0.63
	20	20	58	24	1.2	0.41
3	1	20	20	28.2	1.41	1.41
	5	20	28	29.4	1.47	1.05
	10	20	38	30.4	1.52	0.80
	20	20	58	32	1.60	0.55
4	1	20	20	30.4	1.52	1.52
	5	20	28	32.2	1.61	1.15
	10	20	38	34.2	1.71	0.90
	20	20	58	36.5	1.82	0.63

$L_o$  = length of continuous rod/collapsed length of segmented rod.

L = extended length of segmented rod.



INTENTIONALLY LEFT BLANK.

#### 4. REFERENCES

1. Charters, A. "The Penetration of Rolled Homogenous Armor by Continuous and Segmented Rods at High Velocity: Theory and Experiments." CR-86-1031, General Research Corporation Technical Report, April 1986.
2. de Rosset, W. "Multiple Impacts on Monolithic Steel." Proceedings of the Sixth International Symposium on Ballistics, Orlando, FL, October 1981.
3. de Rosset, W. and K. D. Kimsey. "Calculation of Multiple Copper Rod Impacts on Steel Targets." Proceedings of the Ninth International Symposium on Ballistics, Shrivenham, U. K., May 1986.
4. Eichelberger, R. J. "Experimental Test of Penetration by Metallic Jets." *Journal of Applied Physics* Volume 27, No. 1, pp. 63-68, 1956.
5. Frank, K. "Segmented Penetrators." BRL Memorandum for Record, May 30, 1985.
6. Herbertte, G. "Influence of Projectile Shape on Penetration Power." Proceedings of the 11th International Symposium on Ballistics, Belgium, May 1989.
7. Johnson, G. R. "EPIC-2, A Computer Program for Elastic-Plastic Impact Computations in Two Dimensions Plus Spin." BRL-CR-00373, U. S. Army Ballistic Research Laboratory, Aberdeen Proving Ground, MD, June 1978.
8. Kimsey, K. D. and J. A. Zukas. "Contact Surface Erosion for Hypervelocity Problems." BRL-MR-3495, U. S. Army Ballistic Research Laboratory, Aberdeen Proving Ground, MD, February 1986.
9. Kivity, Y., E. Yitzhak, and E. Hirsch. "Segmented Rods into Homogeneous Targets." Proceedings of the 11th International Symposium on Ballistics, Belgium, May 1989.
10. Kucher, V. "Multiple Impacts on Monolithic Steel." BRL-TR-02406, U. S. Army Ballistic Research Laboratory, Aberdeen Proving Ground, MD, April 1982.

11. Matuska, D. A. and J. J. Osborn. "HULL Documentation: Volume I - HULL Technical Manual; Volume II - HULL User's Manual; Volume III - SAIL User's Guide." Orlando Technology Inc., Shalimar, FL, 1987.
12. Nicholas, T. "Dynamic Tensile Testing of Structural Materials Using a Split Hopkinson Bar Apparatus." AFWAL-TR-80-4053, Air Force Wright Aeronautical Center, Wright-Patterson AFB, Dayton, OH, October 1980.
13. Raatschen, H-J., W. Pavel, S. Fuchs, H. Senf and H. Rothenhausler. "Penetration Efficiency of Segmented Rods." Proceedings of the 11th International Symposium on Ballistics, Belgium, May 1989.
14. Scheffler, D. R., "Two-Dimensional Computer Simulations of Segmented Penetrators." BRL-TR-3013, U. S. Army Ballistic Research Laboratory, Aberdeen Proving Ground, MD, July 1989.
15. Sedgwick, R. T., J. L. Waddell, and G. M. Wilkinson. "High Velocity Long Rod Impact: Theory and Experiment." Proceedings of the Tenth International Symposium on Ballistics, San Diego, CA, October 1987.

No of Copies	Organization
(Class., unlimited) 12	Administrator
(Class., limited) 2	Defense Technical Info Center
(Classified) 2	ATTN: DTIC-DDA Cameron Station Alexandria, VA 22304-6145
1	HQDA (SARD-TR) WASH DC 20310-0001
1	Commander US Army Materiel Command ATTN: AMCDRA-ST 5001 Eisenhower Avenue Alexandria, VA 22333-0001
1	Commander US Army Laboratory Command ATTN: AMSLC-DL Adelphi, MD 20783-1145
2	Commander Armament RD&E Center US Army AMCCOM ATTN: SMCAR-MSI Picatinny Arsenal, NJ 07806-5000
2	Commander Armament RD&E Center US Army AMCCOM ATTN: SMCAR-TDC Picatinny Arsenal, NJ 07806-5000
1	Director Benet Weapons Laboratory Armament RD&E Center US Army AMCCOM ATTN: SMCAR-CCB-TL Watervliet, NY 12189-4050
1	Commander US Army Armament, Munitions and Chemical Command ATTN: SMCAR-ESP-L Rock Island, IL 61299-5000
1	Commander US Army Aviation Systems Command ATTN: AMSAV-DACL 4300 Goodfellow Blvd. St. Louis, MO 63120-1798
1	Director US Army Aviation Research and Technology Activity Ames Research Center Moffett Field, CA 94035-1099

No of Copies	Organization
1	Commander US Army Missile Command ATTN: AMSMI-RD-CS-R (DOC) Redstone Arsenal, AL 35898-5010
1	Commander US Army Tank-Automotive Command ATTN: AMSTA-TSL (Technical Library) Warren, MI 48397-5000
1	Director US Army TRADOC Analysis Command ATTN: ATAA-SL White Sands Missile Range, NM 88002-5502
(Class. only) 1	Commandant US Army Infantry School ATTN: ATSH-CD (Security Mgr.) Fort Benning, GA 31905-5660
(Unclass. only) 1	Commandant US Army Infantry School ATTN: ATSH-CD-CSO-OR Fort Benning, GA 31905-5660
(Class. only) 1	The Rand Corporation P.O. Box 2138 Santa Monica, CA 90401-2138
1	Air Force Armament Laboratory ATTN: AFATL/DLODL Eglin AFB, FL 32542-5000
	<u>Aberdeen Proving Ground</u> Dir, USAMSAA ATTN: AMXSY-D AMXSY-MP, H. Cohen Cdr, USATECOM ATTN: AMSTE-TO-F Cdr, CRDEC, AMCCOM ATTN: SMCCR-RSP-A SMCCR-MU SMCCR-MSI Dir, VLAMO ATTN: AMSLC-VL-D

<u>No. of Copies</u>	<u>Organization</u>
1	Commander Armament RD&E Center US Army AMCCOM ATTN: SMCAR-FSA-E, Dr. W. P. Dunn Bldg. 329 Picatinny Arsenal, NJ 07806-5000
1	Commandant US Army Armor Center ATTN: ATSB-CD, Mr. Dale Stewart Ft. Knox, KY 40121
2	AFATL/DLJW ATTN: Dr. W. Cook Mr. M. Nixon Eglin AFB, FL 32542-5000
2	MSD/ENL ATTN: Mr. W. Dyess Mr. I. Talbot Eglin AFB, FL 32542-5000
4	Naval Surface Warfare Center ATTN: Paula Walter Lisa Mensi Kenneth Kiddy F. J. Zerilli 10901 New Hampshire Avenue Silver Spring, MD 20903-5000
1	Defense Nuclear Agency ATTN: MAJ James Lyon 6801 Telegraph Road Alexandria, VA 22192
2	Director Defense Advanced Research Projects Agency ATTN: Dr. J. Richardson MAJ R. Lundberg 1400 Wilson Blvd. Arlington, VA 22209-2308
2	Lawrence Livermore National Laboratories ATTN: L-290, Dr. Albert Holt Dr. John E. Reaugh P.O. Box 808 Livermore, CA 94550

<u>No. of Copies</u>	<u>Organization</u>
4	Sandia National Laboratories ATTN: Dr. R. Graham (Div. 1551) Dr. J. Hickerson (Div. 9122) Dr. A. E. Hodapp, Jr. (Div. 1551) Dr. R. Lafarge (Div. 1551) P.O. Box 5800 Albuquerque, NM 87185
3	Los Alamos National Laboratory ATTN: Dr. R. Karpp (MS P940) Dr. E. Cort Dr. M. Burkett P.O. Box 1663 Los Alamos, NM 87545
2	Orlando Technology, Inc. ATTN: D. Matuska J. Osborn P.O. Box 855 Shalimar, FL 32579
2	General Research Corporation ATTN: A. Charters T. Menna 5383 Hollister Avenue Santa Barbara, CA 93160-6770
1	General Dynamics ATTN: J. H. Cuadros P.O. Box 50-800 Mail Zone 601-87 Ontario, CA 91761-1085
1	Honeywell, Inc. ATTN: G. R. Johnson 7225 Northland Drive Brooklyn Park, MN 55428
1	Systems, Science & Software, Inc. ATTN: Dr. R. Sedgwick 3398 Carmel Mountain Road San Diego, CA 92121
2	California Research & Technology, Inc. ATTN: Mr. Roland Franzen Dr. Dennis Orphal 5117 Johnson Drive Pleasanton, CA 94566

<u>No. of Copies</u>	<u>Organization</u>
5	LTV Missiles & Electronics Group ATTN: Dr. Gary Hough (WT-50) Mr. K. W. Havens (EM-36) Dr. G. L. Jackson (WT-71) Mr. R. J. Taylor (EM-36) Dr. M. M. Tower (WT-78) P.O. Box 65003 Dallas, TX 75265-0003
3	Kaman Sciences Corporation ATTN: D. Barnette D. Elder P. Bussell P.O. Box 7463 Colorado Springs, CO 80933

INTENTIONALLY LEFT BLANK.

USER EVALUATION SHEET/CHANGE OF ADDRESS

This Laboratory undertakes a continuing effort to improve the quality of the reports it publishes. Your comments/answers to the items/questions below will aid us in our efforts.

1. BRL Report Number BRL-TR-3081 Date of Report FEB 90
2. Date Report Received \_\_\_\_\_
3. Does this report satisfy a need? (Comment on purpose, related project, or other area of interest for which the report will be used.) \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_
4. How specifically, is the report being used? (Information source, design data, procedure, source of ideas, etc.) \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_
5. Has the information in this report led to any quantitative savings as far as man-hours or dollars saved, operating costs avoided or efficiencies achieved, etc? If so, please elaborate. \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_
6. General Comments. What do you think should be changed to improve future reports? (Indicate changes to organization, technical content, format, etc.) \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

CURRENT ADDRESS

Name	_____
Organization	_____
Address	_____
City, State, Zip	_____

7. If indicating a Change of Address or Address Correction, please provide the New or Correct Address in Block 6 above and the Old or Incorrect address below.

OLD ADDRESS

Name	_____
Organization	_____
Address	_____
City, State, Zip	_____

(Remove this sheet, fold as indicated, staple or tape closed, and mail.)



— — — — — FOLD HERE — — — — —

Director  
U.S. Army Ballistic Research Laboratory  
ATTN: SLCBR-DD-T  
Aberdeen Proving Ground, MD 21005-5066




NO POSTAGE  
NECESSARY  
IF MAILED  
IN THE  
UNITED STATES

OFFICIAL BUSINESS

**BUSINESS REPLY MAIL**  
FIRST CLASS PERMIT NO 12062 WASHINGTON, DC  
POSTAGE WILL BE PAID BY DEPARTMENT OF THE ARMY

Director  
U.S. Army Ballistic Research Laboratory  
ATTN: SLCBR-DD-T  
Aberdeen Proving Ground, MD 21005-9989



— — — — — FOLD HERE — — — — —